STAGE 2 WIP COST PLAN

Trehus

New Build Office

9th May 2023

www.circledevelopment.co.uk

Trehus, Maidenhead
Stage 2 WIP Cost Plan
9 May 2023

TOTAL GIFA	
7,750	m2
83,421	ft2

CIRCLE

OVERALL PROJECT ELEMENTAL ANALYSIS

	Element	%	Elemental Cost £	Cost / m² Gross £	Cost / ft² Gross £	%
1	**SUBSTRUCTURE**					**4.8%**
1.10	Substructure		1,098,150	141.70	13.16	4.8%
2	**SUPERSTRUCTURE**		**8,685,640**			**37.8%**
2.10	Frame		3,381,540	436.32	40.54	14.7%
2.20	Upper floors		23,040	2.97	0.28	0.1%
2.30	Roof		214,520	27.68	2.57	0.9%
2.40	Stairs and ramps		307,500	39.68	3.69	1.3%
2.50	External Walls		4,257,930	549.40	51.04	18.5%
2.60	Windows and external doors		18,000	2.32	0.22	0.1%
2.70	Internal walls and partitions		297,110	38.34	3.56	1.3%
2.80	Internal doors		186,000	24.00	2.23	0.8%
3	**INTERNAL FINISHES**		**1,524,680**			**6.6%**
3.10	Wall finishes		301,230	38.87	3.61	1.3%
3.20	Floor finishes		1,051,570	135.69	12.61	4.6%
3.30	Ceiling finishes		171,880	22.18	2.06	0.7%
4	**FITTINGS, FURNISHINGS AND EQUIPMENT**					**1.2%**
4.10	Fittings and Fixtures		281,220	36.29	3.37	1.2%
5	**SERVICES**		**6,135,480**			**26.7%**
5.01	Sanitary appliances		-	-	0.00	0.0%
5.02	Service equipment		255,000	32.90	3.06	1.1%
5.03	Disposal installations		52,150	6.73	0.63	0.2%
5.04	Water installations		-	-	0.00	0.0%
5.05	Heat source		-	-	0.00	0.0%
5.06	Space heating and air conditioning		1,075,520	138.78	12.89	4.7%
5.07	Ventilation systems		1,107,020	142.84	13.27	4.8%
5.08	Electrical installations		1,657,830	213.91	19.87	7.2%
5.09	Gas and other fuel installations		-	-	0.00	0.0%
5.10	Lift and conveyor installations		313,500	40.45	3.76	1.4%
5.11	Fire and lightning protection		785,820	101.40	9.42	3.4%
5.12	Communications, security and control systems		56,890	7.34	0.68	0.2%
5.13	Specialist installations		54,000	6.97	0.65	0.2%
5.14	Builders's work in connection		149,710	19.32	1.79	0.7%
5.15	Testing and commissioning		628,040	81.04	7.53	2.7%
6	**COMPLETE BUILDING AND BUILDING UNITS**		**-**	**0.00**	**0.00**	**0.0%**
7	**WORK TO EXISTING BUILDINGS**		**-**	**0.00**	**0.00**	**0.0%**
8	**EXTERNAL WORKS**		**682,610**	**88.08**	**8.18**	**3.0%**
9	**FACILITATING WORKS**		**115,000**	**14.84**	**1.38**	**0.5%**
	SUB-TOTAL BUILDING CONSTRUCTION COST		**18,522,780**	**2,390**	**222**	**81%**
	On Costs					
10	**Contractor's preliminaries**	**15%**	**2,818,490**	**363.67**	**33.79**	**12%**
11	**Main contractor's overheads and profit**	**5%**	**1,067,060**	**137.68**	**12.79**	**5%**
12	**Project / design team fees**	**Excluded**	**-**	**0.00**	**0.00**	**0%**
13	**Design development contingency**	**3%**	**560,210**	**72.28**	**6.72**	**2%**
14	**Inflation to Mid-Point**	**Excluded**	**-**	**0.00**	**0.00**	**0%**
	TOTAL CONSTRUCTION COST		**22,968,540**	**2,964**	**275**	**100%**

Detailed Analysis of Costs

	Description		Quantity	Unit	Rate / £	Total / £
1.1	Substructure					
	Substructure					
	Cut / Fill					
	Cut to formation level; 1,000mm Ground Floor Raft Slab	1	1,287	m3	55	70,806
	Bulk excavation to External Works	0.6	542	m3	55	29,825
	Disposal off site, inert material (Assume cut can be used as fill)		1,830	m3	45	82,335
	- e/o for contaminated, non-hazardous;		-	m3	67	Excluded
	- e/o for contaminated, hazardous;		-	m3	343	Excluded
	Allowance for removal of surface water from excavations		1	Item	5,000	5,000
	Allowance for removal of obstructions from excavations		1	Item	10,000	10,000
	Ground Floor Slab					
	Ground floor RC raft foundation slab; 1,000mm thick RC slabs; 100kg/m3 reinforcement; including waterproofing; including blinding and insulation		1,287	m2	647	832,478
	Allowance for Gas Membrane; Taped Visqueen Gas Membrane	Assume Not Required				Excluded
	Allowance for strengthening					
	100mm Hardcore to soft spots	0.25	322	m3	55	17,702
	Crane bases					
	Crane bases; allowance		1	nr	40,000	40,000
	Lift pits					
	Lift pits; allowance	Formed Above Ground	2	nr	5,000	10,000
2.1	Frame					
	Frame					
	CLT, Glulam and Steel Frame					
	CLT Non-visual Material; predominantly whitewood spruce Non-Visual CLT; including associated proprietary fixing brackets, screws and sealing tapes		7,311	m2	167	1,220,215
	e/o for one side Industrial Visual Material; BC lamellas		7,311	m2	13	96,045
	Breather Membrane to CLT; floors and roof		6,707	m2	14	92,425
	Glulam: design, management, manufacture, supply and delivery; Whitewood spruce glulam		828	m2	1,562	1,293,440
	Finishing Connections		1	item	32,910	32,910
	Structural Steel; Including Intumescent Paint		3	tn	5,372	18,425
	Concrete drilling and resins to the concrete core; M16x125		528	nr	39	20,485
	Cast in plates; connections between concrete core and structural beam		1	item	16,945	16,945
	Erection of Frame		1	item	295,325	295,325
	Supply and fit of level 5 timber pergola; Larch timber		1	item	27,450	Excluded
	RC core walls					
	Core; 250mm thick reinforced concrete frame; 200kg/m³ reinforcement; assumed C50/C60 concrete grade		731	m2	307	295,325
2.2	Upper floors					
	Upper Floors					
	Timber CLT soffit, exposed finish - included in section 2.1					Included
	RC Slabs - First and Second Floor Slabs					
	250mm thick reinforced concrete; 200kg/m³ reinforcement; assumed C50/C60 concrete grade		142	m2	162	23,040
2.3	Roof					
	Roof					
	Generally					
	CLT roof deck included in section 2.2					Included
	Generally - finishes to roof		1,079	m2	150	161,804
	e/o for Green Roof					Excluded
	Ancillaries					
	Mansafe system including anchor points		1	nr	25,000	25,000
	Rainwater installations		197	m	90	17,712

Detailed Analysis of Costs

	Description		Quantity	Unit	Rate / £	Total / £
	Other:					
	Lift Overun included in section 2.2					Included
	Allowance for access hatch to roof		1	nr	10,000	10,000
2.4	Stairs and ramp					
	Stairs and Ramp					
	Precast concrete stair to core; includes all finishes					
	PCC stairs, landings, handrails & balustrading		5	stry	11,500	57,500
	Feature Timber Stair; including all finshes					
	Steel stair cladded in timber; including timber handrails & steel balustrading - double landing		5	stry	50,000	250,000
2.5	External walls					
	External Walls					
	Façade - EWS1 A1/A2 Façade - NOTE: Excludes Window Openings & EPDM as Regs					
	Solid Façade Groud Floor - Massangis Beige Brick; 600x450x102		221	m2	961	212,640
	Solid Façade - Polycor Natural Stone Brick; Earth Blend; 215x102.5x65		1,281	m2	917	1,174,817
	Allowance for deep reveals; Polycor Brick Natural Stone Brick; Earth Blend; 215x102.5x65		523	m2	917	479,169
	Mesh Enclosure to Roof Plant Area	Assumed 1.5m High	102	m2	550	56,100
	Ground floor plant louvered extract		32	m2	800	25,344
	Enhanced finish to soffit of ground floor entrance		75	m2	1,000	75,000
	Timber Cladding to Entrance Columns; Ground floor		17	m2	650	10,725
	Glazing					
	Curtain Walling to Ground Floor		358	m2	1,200	430,056
	Glazing; Aluminium Windows		1,350	m2	1,175	1,586,767
	E/O Glass to glass corner detail		76	m	1,000	75,600
	Terrace Area - Level 5					
	Allowance for brick parapet		128	m2	917	117,009
	Allowance for thermal lining		42	m	350	14,700
	Floor finish					Included
2.6	Windows and external doors					
	Windows and other glazed systems					
	Included in section 2.5 above					
	External Doors; Assumed					
	e/o Entrance Sliding Doors - Double; Fully Glazed; Automated		2	nr	3,000	6,000
	e/o Ground Floor Doors; Single		4	nr	200	800
	e/o Ground Floor Louvred Doors to Plant; Double		1	nr	200	200
	e/o Ground Floor Doors to Refuse/Cycle Store; Single		4	nr	250	1,000
	e/o External Door to Level 5 Terrace Area; Double; Fully Glazed		4	nr	2,500	10,000
2.7	Internal walls and partitions					
	Internal walls and partitions					
	Composite Item, dividing walls; stud partition, frame, insulation, plasterboard					
	Core Wall Lining; Plasterboard		680	m2	55	37,397
	Remaining Core Walls; Included in Seciton 2.2 - CLT		1,386	m2	115	Excluded
	WC Partitioning		514	m2	110	56,530
	e/o moisture board to WC and showers		1,027	m2	15	15,410
	Perimeter Wall Lining; Plasterboard		1,502	m2	85	127,702
	Blockwork to BOH area; Ground Floor		495	m2	95	46,986
	Allowance for durasteel to substation		52	m2	250	13,082

Detailed Analysis of Costs

	Description	Quantity	Unit	Rate / £	Total / £
2.8	Internal doors				
	Internal doors				
	Commercial				
	Doorsets; to include frame, leaf, ironmongery and decoration				
	Corridor Doors; Single Leaf	42	nr	1,200	50,400
	Plant Doors; Double Leaf	12	nr	2,500	30,000
	Riser Doors ; FD120S; Assumed Double	12	nr	2,500	30,000
	WC Doors; Single Leaf	48	nr	1,200	57,600
	Stair Core; Single Leaf	6	nr	1,500	9,000
	Plant Doors; Singel Leaf	6	nr	1,500	9,000
3.1	Wall finishes				
	Wall finishes				
	Composite Item				
	Allowance for fire retardant clear lacquer; Walls and Columns	4,441	m2	20	88,825
	Allowance for Painted wall finish	4,094	m2	12	49,123
	Painted Wall to WC & Showers	514	m2	90	46,231
	Tiled Wall Finishes to WC & Showers	514	m2	150	77,051
	E/o for enhanced finish to the entrance / reception	1	Item	40,000	40,000
3.2	Floor finishes				
	Floor finishes				
	Communal areas				
	Raised Access Flooring; 150mm	7,190	m2	60	431,389
	Allowance for 38mm ply board	6,463	m2	20	129,254
	Allowance for resilient layer; Assumed GenieMat FF25 25mm	6,463	m2	58	374,836
	Carpet; to office area	6,466	m2	35	Excluded
	Tiled porcelain flooring to bathroom areas	210	m2	120	25,184
	Enhanced finish to circulation space; stair core; Ground Reception to first floor	273	m2	250	68,335
	Carpet to circulation space; stair core; second to fifth	154	m2	35	5,375
	Painted finish to BOH Areas	248	m2	15	3,721
	Screed to communal areas	337	m2	40	13,479
3.3	Ceiling finishes				
	Ceiling finishes				
	Composite Item				
	Allowance for specialist CLT Ceiling Finish - exposed CLT soffit to all areas; excluding WC's	7,540	m2	20	150,804
	Acoustic Rafts				Excluded
	Suspended ceiling to bathroom area	210	m2	50	10,494
	Painted plasterbaord to WC & Shower area	210	m2	15	3,148
	e/o moisture board to showers	210	m2	15	3,148
	Allowance for durasteel to substation	17	m2	250	4,283
4.1	General fittings, furnishings and equipment				
	General FF&E				
	Bathroom Cubicles - Sanitaryware Only				
	WC - Self Contained Unisex				
	Toilet Unit	27	nr	329	8,883
	Handwash basin & tap	27	nr	357	9,639
	Mirror	27	nr	214	5,778
	Hand dryer	27	nr	910	24,557
	Misc. Toilet brush, toilet roll holder	27	nr	76	2,054
	Boxing out to toilet	27	nr	696	18,779
	Vanity top to worktop	27	nr	589	15,890
	Push Flush Plate	27	nr	39	1,040
	Integrated soap dispenser	27	nr	48	1,304
	Brushed Stainless steel bottle trap & Extension	27	nr	54	1,455
	Allowance for connection, testing & Commissioning	27	nr	600	16,200

Detailed Analysis of Costs

	Description		Quantity	Unit	Rate / £	Total / £
	WC - Self Contained Unisex - Oversized					
	Large Mirror		6	nr	375	2,247
	Small Mirror		6	nr	214	1,284
	Toilet Unit		6	nr	329	1,974
	Washing Basin & Tap		6	nr	357	2,142
	Hand dryer		6	nr	910	5,457
	Misc. Toilet brush, toilet roll holder		6	nr	76	456
	Boxing out to toilet		6	nr	696	4,173
	Vanity top to worktop		6	nr	589	3,531
	Push Flush Plate		6	nr	39	231
	Integrated soap dispenser		6	nr	48	290
	Brushed Stainless steel bottle trap & Extension		6	nr	54	323
	Allowance for connection, testing & Commissioning		6	nr	600	3,600
	Acc. WC - Self Contained Unisex					
	Large Mirror		7	nr	375	2,622
	Small Mirror		7	nr	214	1,498
	Toilet Unit		7	nr	329	2,303
	Washing Basin & Tap		7	nr	357	2,499
	Wall-mounted grab rail		7	nr	134	936
	Hand dryer		7	nr	910	6,367
	Misc. Toilet brush, toilet roll holder		7	nr	76	533
	Boxing out to toilet		7	nr	696	4,869
	Vanity top to worktop		7	nr	589	4,120
	Push Flush Plate		7	nr	39	270
	Integrated soap dispenser		7	nr	48	338
	Brushed Stainless steel bottle trap & Extension		7	nr	54	377
	Allowance for connection, testing & Commissioning		7	nr	600	4,200
	Self Contained Unisex Showers to Ground floor					
	Shower Unit		6	nr	2,486	14,915
	Shower Tray		6	nr	663	3,980
	Shower Screen		6	nr	882	5,290
	Bench		6	nr	321	1,926
	Mirror		6	nr	214	1,284
	Misc. Hooks and dispensers		6	nr	115	687
	Brushed Stainless steel bottle trap & Extension		6	nr	54	323
	Allowance for connection, testing & Commissioning		6	nr	600	3,600
	Signage					
	Statutory Signage		1	Item	15,000	15,000
	Way finding signage		1	Item	20,000	20,000
	Cycle Stores					
	Cycle racks		56	nr	250	14,000
	E-Bike stand			nr	770	Excluded
	Euro Bins	Allowance	8	nr	1,000	8,000
	Lockers					Excluded
	Parcels					
	Storage Racking					Excluded
	Blinds					
	To all windows					Excluded
	Kitchen					
	Kitchenette or café					Excluded
	Reception					
	Allowance for Reception Desk		1	item	30,000	30,000
	Allowance for Furniture to Entrance					Excluded
5.01	Sanitary appliances					
	Refer to FF&E					

Detailed Analysis of Costs

	Description		Quantity	Unit	Rate / £	Total / £
5.02	Service equipment					
	Domestic Services		83,421	ft2	3	255,005
5.03	Disposal installations					
	Above Ground Drainage		83,421	ft2	1	52,147
						-
5.04	Water installations					
						-
5.05	Heat source					
						-
5.06	Space heating and air conditioning					
	2 Pipe Hybrid VRF System		83,421	ft2	13	1,075,523
5.07	Ventilation systems					
	Mechanical Ventilation					
	Ventilation Systems		83,421	ft2	12	1,001,053
	Ductwork		83,421	ft2		Included
	Smoke Vent		83,421	ft2	0.92	76,976
	Dry Risers		83,421	ft2	0.35	28,991
5.08	Electrical installations					
	Electrical installations					
	Mains Distribution		83,421	ft2	6	471,689
	Main Electrical Containment		83,421	ft2	4	307,349
	Small Power		83,421	ft2	2	203,253
	Lighting		83,421	ft2	8	675,535
5.09	Gas and other fuel installations					
5.10	Lift and conveyor installations					
	Passenger Lifts					
	Firefighting High Speed Passenger Lifts; 13 person; Nr of Stops; 2m/s		18	nr	15,000	270,000
	Additional lift door to firefighting lift		6	nr	7,250	43,500
5.11	Fire and lightning protection					
	Sprinklers System		83,421	ft2	7	583,948
	Fire Detection		83,421	ft2	2	197,920
	Lightning Protection		83,421	ft2	0.05	3,950
	Fire Curtains to Primary Stair Core			nr	2,500.00	Excluded
5.12	Communications, security and control systems					
	CCTV / Data		83,421	ft2	0.15	12,247
	Access Control		83,421	ft2	0.38	31,999
	Disabled refuge and toilet alarms		83,421	ft2	0.15	12,642
5.13	Specialist installations					
	Photovoltaic Panels		120	nr	450	54,000
5.14	Builders' work in connection					
	BWIC with M&E works		3%		4,990,226	149,707
5.15	Testing and commissioning etc					
	Electrical Testing and Commissioning		83,421	ft2	0.36	29,629
	Mechanical Testing and Commissioning		83,421	ft2	1	65,183
	Mechanical & Electrical Preliminaries		10%		5,332,245	533,224
6	Complete building and building units					
						-
7	Work to existing buildings					
						-

TOTAL GIFA
7,750 m2
83,421 ft2

CIRCLE

Detailed Analysis of Costs

	Description		Quantity	Unit	Rate / £	Total / £
8	External Works					
	Hard Landscaping; Generally					
	General Allowance		609	m2	250	152,253
	Pedestrian Path		79	m2	220	17,424
	Block Paving to terrace		247	m2	250	61,753
	Soft Landscaping; Generally					
	General Allowance		295	m2	150	44,217
	Tables and Chairs		1	item	15,000	Excluded
	Trees		14	nr	1,200	16,800
	Allowance for 278 Works		156	m2	200	31,252
	External Lighting		983	m2	80	78,639
	Site drainage					
	Foul Water (Including excavation / cartaway)		94	m	350	32,900
	Surface Water; 150mm (Including excavation / cartaway)		80	m	300	23,970
	Surface Water; 225mm (Including excavation / cartaway)		43	m	325	14,008
	Surface Water; 375mm (Including excavation / cartaway)		22	m	350	7,665
	Surface Water Packing Pump Station; 14l/s		1	nr	25,000	25,000
	Surface Water manhole		6	nr	4,500	27,000
	Foul Water sewer manhole		13	nr	4,500	58,500
	Linear Channel with Heelguard Grating		65	m	210	13,734
	Allowance for reuse of existing foul water outfall; including connections		1	item	10,000	10,000
	Attenuation Tank					
	General allowance		150	m3	450	67,500
9	Facilitating works					
	Demolition and alterations					
	General Site Clearance of Site Remains / Vegetation				Excluded	Excluded
	Incoming service connections and disconnections					
	Electricity - Allowances					
	Electrical Supply installations		1	Item	60,000	60,000
	Substation		1	Item	Included	Included
	Gas					
	Gas Disconnection / Connection for boilers (Not required)					Excluded
	Potable Water					
	Incoming Water Connection		1	Item	30,000	30,000
	Potable Water - Reinforcement Works					
	Upgrade of existing network					Excluded
	Foul Water					
	Foul Water Connection	*Existing Connection*	1	Item	10,000	10,000
	BT / Hyperoptic / Virgin Media					
	BT or similar connection		1	Item	15,000	15,000
	Moving/relocating existing services					
	General allowance					Excluded
	Oversailing License Allowance					
	General allowance - Excluded					Excluded

Trehus, Maidenhead
Stage 2 WIP Cost Plan
9 May 2023

TOTAL GIFA
7,750 m2
83,421 ft2

CIRCLE

	Detailed Analysis of Costs					
	Description		Quantity	Unit	Rate / £	Total / £
10	Contractor's preliminaries					
	Main Contractors Preliminaries - assuming a programme overlap with the One Maidenhead residential scheme, utilising the same Main Contractor. Note - One Maidenhead completes Q3 2024	15%	1	item	18,522,760	2,818,487
11	Main contractor's overheads and profit					
	Main Contractors OH&P	5%	1	item	21,341,247	1,067,062
12	Project / design team fees					
	Design fees (Excluded)			Excl		-
13	Design development contingency					
	Contractors Design Contingency - Likely % based upon RIBA Stage 3 information.					
	Main Contractors Contingency	2.50%	1	item	22,408,310	560,208
14	Inflation					
	Inflation to Mid-Point of Construction as Q3 2023				Excluded	-

Trehus, Maidenhead

Unit and Area Schedule

9 May 2023

CIRCLE

Area and Unit Shedule

Location		Circulation				Ancillary					External	**Total**	
	Office Area	Demising Walls	Stair Core	Lift Core	Lobby / Corridor / Reception	Riser	Plant	Retail A1/A5/B1/D1/D2	WC	BOH	External Terrace Area	**NIA**	**GIA**
	m2	m2	m2	m2	m2	m2	m2	m2	m2	m2	m2	**Total**	**Total**
Ground Floor	696	31	25	10	225	8	10	0	35	248	0	696	1,287
Level 1	1,208	26	22	10	28	7	10	0	35	0	0	1,208	1,346
Level 2	1,208	26	22	10	28	7	10	0	35	0	0	1,208	1,346
Level 3	1,208	26	22	10	28	7	10	0	35	0	0	1,208	1,346
Level 4	1,208	26	22	10	28	7	10	0	35	0	0	1,208	1,346
Level 5	940	25	23	10	28	7	10	0	35	0	247	940	1,079
Level 6 - Roof	0	0	0	0	0	0		0	0	0	0	0	0
Total	6,466	159	137	62	365	45	58	0	210	248	247	6,466	7,750