gleeds

TWCM0743 - Hadden Hill, Didcot ; Drive To

Stage 2 - Cost Plan

August 2024

Martin Properties
36 Walpole Street
London, SW3 4QS

Gleeds Cost Management
Trinity House, Church Road,
Tunbridge Wells, Kent, TN1 1AG

TWCM0743
Confidential

Contents

Document Control	Page 3
Basis and Assumptions	Page 4-5
Schedule of Areas	Page 6
Summary	Page 7
RIBA Stage 2 - Cost Plan	Pages 8-10
Schedule of Inclusions and Exclusions	Pages 11-12

Document Control

gleeds

Identification

This Project Document is categorised as follows:

Category	Details
Report Type:	RIBA Stage 2 - Cost Plan
Report No.:	01
Version No.:	2
Project Name:	Hadden Hill Retail Park, Didcot - Drive To Option
Project No.:	TWCM0743
Classification:	Confidential - To Client
Author:	Sam Stevens
Reviewed:	Ben Smith

Document Approval

Project Document approved by:

Name	Position	Signature	Date
Steve Sawyer	Director		16/08/2024

Document Distribution

This Project Document is categorised as follows:

Name	Organisation	Role
Matt Bird	Martin Properties	Senior Development Manager
Chris Darke	Martin Properties	Design Manager
Daniel Gaunt	Childerstone	Director

Basis and Assumptions

1 **Cost Plan Base Date**

This Cost Plan has been prepared using rates and prices current at the time the cost plan was produced – referred to as the Cost Plan base date.

The 'Cost Plan Base Date' is August 2024.

2 **Procurement and Contract Strategy**

The Costings are based on:
- The tender price/contract sum being obtained through single stage competitive tendering;
- The use of a design and build form of contract with non-significant amendments;
- Liquidated damages being set at levels that are commercially acceptable to contractors;
- The works are constructed as one phase of works.

3 **Unit Rates**

Unit rates for building works items exclude any allowance for main contractor's preliminaries and main contractor's overheads and profit, an separate allowance is included for those items.

4 **Project and Design Fees**

No allowances are included for Project or Design Team Fees, as listed below (please note this is not an exhausted list but for general understanding):
- Project team and design team consultants' pre-novation fees;
- Other consultants' fees;
- Site investigation and survey fees including archaeological works;
- Planning fees or contributions;
- Building Regulation fees; and
- Marketing Costs etc.

5 **Risk Allowances**

Risk Allowances have been determined and included in this cost plan as follows:

Design Development Risks:	0.00% (Excluded)
Construction Cost Risks:	5.00%
Employer's Change Risks:	0.00% (Excluded)
Employer Other Risks:	0.00% (Excluded)

It has been assumed that Martins Properties will be looking to achieve cost reductions through appropriate value engineering during further stages of design development. In view of this, no risk allowance has been included in this cost plan for reduction costs due to such design development.

No allowances have been included in this cost plan for either employer's change risks or employer's other risks. It is therefore, recommended that Martins Properties make sufficient budgetary allowances for both categories of risk in their investment or development appraisal for the project.

6 **Documents used in production of Cost Plan**

See document list section for the drawings, specifications and information documents this Cost Plan is based upon.

7 **Inclusions, Exclusions and assumptions**

The pricing basis of this preliminary budget estimate is current market conditions and should be reviewed at regular intervals of no longer than 1 month.

The construction costs included within this report are based on a model cost plan utilising the areas and floorplans provided to us but with
We have included utilities quotes provided (water, electricity, & gas) and are up to date as of when Cost Plan was created.
We have assumed that the works will be procured by competitive tender.
We have assumed all arisings are inert.
We have used the GIFA as stated on The Harris Partnerships drawings.
We have assumed the buildings are built to shell only, with capped services.
The pricing basis of this document is current market conditions and should be reviewed at regular intervals of no longer than 1 month.
GIFA measured using the RICS NRM Code of Measuring Practice (6th Edition).

Unless specifically identified elsewhere in these costings, no allowance has been made for any projects costs that are not directly associated with works costs or project and design fees, but form part of the total cost of the building project to the employer; for example, insurances, planning fees, fees in connection with party wall awards, decanting and relocation etc.

It is advocated that Martins Properties make sufficient budgetary allowances for all excluded items in their investment or development appraisal for the project.

An indicative list of the items included in and excluded from this Cost Plan; together with items that are considered to be not applicable to this project is in the Schedule of Inclusions and Exclusions section of this report.

8 **Disclaimer**

This preliminary budget estimate has been prepared from outline information only and we strongly advise that the consultants should be allowed to develop the brief further before any irrevocable financial commitment is entered into by the Client.

Gleeds' construction cost forecasts are based on the latest information available from the supply chain and are current at the date of issue but, by necessity, are subject to alteration due to changing market conditions and other factors and should, therefore, be reviewed regularly and updated accordingly.

Materials prices and labour rates continue to be volatile. Although levels of volatility in materials prices have cooled recently, increases in labour rates linked to inflation still drive price increases. In the UK, the predicted fall in construction output, which tends to stabilise pricing

Basis and Assumptions

levels, has largely not materialised, with widely held expectations of recession not occurring. Nevertheless, forecasts still generally indicate a decrease in construction output for 2024.

As we move into an election year in the UK, US and elsewhere, there are concerns at the prospect of more political change with the potential that the economic policy of the successful party will impact construction output. Elevated levels of insolvency in the supply chain continue to influence the industry, affecting capacity and appetite for risk in some areas.

The gradual reduction in inflation levels supported by a drop in energy prices from previous highs will impact construction costs along with potential interest rate decreases. However, we expect energy prices to remain volatile in the medium to long term, and with unrest in large parts of the world and ongoing political uncertainty, disruption to supply chains is anticipated to continue in 2024.

Project: **Hadden Hill Retail Park, Didcot**
Code: **TWCM0743**
Ref: **Drive to Pod**
RIBA Stage 2 - Cost Plan

gleeds

Schedule of Areas

1 The below indicative areas are included within this Cost Plan, they are merely estimations from the limited information provided.

	Shell	
Internal Areas	GIA m2	GIA ft2
Pod		
Ground Floor	325.00	3,498
Total	325.00	3,498
External Areas		
Car park / hardstandings / soft landscaping	1,209	
Total	1,209	

Project: Hadden Hill Retail Park, Didcot
Code: XSUB2023
Ref: Drive to Pod
RIBA Stage 2 - Cost Plan

gleeds

Overall Summary

Ref	Description	RIBA Stage 2 - Cost Plan	
			£
A	Building Works Cost Plan Total		906,198
	Building Works sub-total		**906,198**
	Constructor's services and on-costs		
B	Main Contractor Preliminaries	11%	99,682
C	Pre-contract design fees	Item	Excluded
D	Pre-contract Survey fees	Item	Excluded
	Sub total	**£**	**1,005,880**
E	Overheads & Profit	6.00%	60,353
	Construction Works Total	**£**	**1,066,233**
F	Design Reserve and Client Contingency	5.00%	53,312
	Total Construction Cost Estimate	**£**	**1,119,544**

Target Value Engineering (VE)	Value (Approximate)
Construction: prefabricated or modular construction	TBA
Construction: target cost for ground floor slab formation ; target rate £150m/2	£20,000
Construction: target cost for lightweight steel frame	£10,000
Construction: alternative product to the aluminium rainscreen cladding	£15,000
Construction: reduce are of glazing to soild wall construction	£25,000
Construction: target cost for roofing ; target rate of £200/m2	£15,000
Construction: target cost for paving ; target rate of £100/m2	£25,000
Layout: reuse existing hardstanding's / substrate	£2,500
Sustainability: alternative methods other than solar panels	£6,750
Maintenance: reduced planting for low maintenance alternative	£2,500
Sub-Total	£121,750
Total Target Value Engineering (incl %'s)	**£150,000**

Project: **Hadden Hill Retail Park, Didcot**

Code: **TWCM0743**

Ref: **Drive to Pod**

RIBA Stage 2 - Cost Plan

gleeds

Item	Description	Quantity	Unit	Rate	Total
	Facilitating / Demolition Works				
1	Removal of existing established trees	7	nr	400	2,800.00
2	Break up existing hardstanding's; pod location	365	m²	65	23,725.00
3	Break up existing hardstanding's; to reduced levels	602	m²	35	21,070.00
4	Remove existing soft landscaping	242	m²		Included
5	Site clearance and levelling; generally	1,209	m²	5	6,045.00
	Substructure				
6	Excavation for foundations; assumed 1m deep	365	m²	55	20,075.00
7	Pads and ground beams	82	m	250	20,500.00
8	Ground floor slab formation - 200mm	365	m²	200	73,000.00
9	Brickwork plinth; say 3 course below and above DPC	76	m	70	5,320.00
	Superstructure				
	Frame				
10	Structural steel frame including fittings based on 50 kg/m2 overall GIFA including fittings	325	m²	175	56,875.00
11	Secondary steelwork, based on an extra 5 kg/m²	325	m²	20	6,500.00
12	Intumescent paint fire protection to steelwork	18	t	320	5,760.00
13	Allowance for miscellaneous works, protecting columns	1	item	1,000	1,000.00
	Roof				
14	Composite roof panel with insulation	460	m²	250	115,000.00
15	Rainwater drainage, gutters and downpipes	460	m²	10	4,600.00
16	Mansafe system	1	item		Excluded
	External Wall, Windows and Doors				
17	Façade type 1; Aluminium Standing Seam	0	m²	550	-
18	Façade type 2; Aluminium Cassettes	34	m²	355	12,070.00
19	Façade type 3; Aluminium Facia	74	m	100	7,400.00
20	Façade type 3a; Timber Soffit to underside of roof	95	m²	125	11,875.00
21	Façade type 4; Micro rib Composite Panel	100	m²	280	28,000.00
22	Façade type 5; Equitone Cement Panel	120	m²	305	36,600.00
23	Façade type 6; Composite Roof Panel (Vertical)	0	m²		-
24	Façade type 7; Proprietary curtain walling including doors	82	m²	800	65,600.00
25	Inner leaf of 140mm thick blockwork	172	m²	100	17,200.00
26	Metsec wall framing above windows	64	m²	55	3,520.00
27	Internal partitions; split tenancy	0	m²		Excluded
28	External doors - Single; Fire exit metal clad door	2	nr	2,500	5,000.00
29	External doors - Main entrance single glazed	2	nr		Included
	Internal Walls and Partitions and Doors				
30	Lining to internal face of external wall	254	m²		Excluded
31	Internal Party walls	0	m²		Excluded
32	Internal doors	0	nr		Excluded
	Internal finishes				
33	Decorations to walling - including plastering, installation and decorations of timber skirtings	254	m²		Excluded
34	Tiled wall finishes, full height	0	m²		Excluded
				Carried Forward £	549,535

Project: **Hadden Hill Retail Park, Didcot**

Code: **TWCM0743**

Ref: **Drive to Pod**

RIBA Stage 2 - Cost Plan

gleeds

Item	Description	Quantity	Unit	Rate	Total
			Brought Forward £		549,535
	Floor finishes				
35	Screeding	325	m²		Excluded
36	Painted finishes	0	m²		Excluded
	Ceiling finishes				
37	Suspended ceilings and finishes	0	m²		Excluded
38	EO allowance for moisture resistant plasterboard ceiling areas	0	m²		Excluded
	FF&E				
39	Signage - Wayfinding	1	item		Excluded
40	Signage - Statutory	1	item	1,500	1,500.00
	Services				
	MEPH				
41	Allowance for temporary lighting, emergency lighting and lighting control	3,498	ft²	1.5	5,247.00
42	Fire alarm interface & smoke detector	3,498	ft²	1.0	3,498.00
43	Small power	1	item		Excluded
44	Access control	325	m²		Excluded
45	WCs	0	nr		Excluded
46	WHB; incl vanity	0	nr		Excluded
47	Accessories	0	nr		Excluded
48	Waste, soil and vent installation; uPVC pipework	4	nr	750	3,000.00
49	Lightning protection - optional requirement	1	item		Excluded
50	PV panels	180	m²	150	27,000.00
51	Builder works in connection with services	325	m²	10	3,250.00
	Utilities				
52	Gas Diversion; SGN quote dated 17/01/24	1	item	29,428	29,428.00
53	New Gas connection	1	item		Excluded
54	Excavation, reinstatement and Traffic management for SSE works	1	item	10,000	10,000.00
55	3 phase supply from sub; SSE quote dated 01/07/24	1	item	25,934	25,934.00
56	Openreach Connect; including ductwork	1	item	2,500	2,500.00
57	Water; Thames Water quote dated 01/03/24	1	item	4,336	4,336.00
58	BWIC; Works relating stats. (PROVISIONAL)	1	PS	5,000	5,000.00
	External works				
	Drainage				
59	Extend and connect foul into existing drain (not to exceed 2m depth)	60	m	200	12,000.00
60	Allowance for new below ground sump chamber & pump	1	item	8,500	8,500.00
61	New foul water drainage to pod	70	m	200	14,000.00
62	Foul water inspection chamber	4	nr	1,750	7,000.00
63	Storm water attenuation; Wavin Aquacell or similar 50m³	1	item	20,000	20,000.00
64	Flow control chamber / hydro brake	1	item	4,500	4,500.00
65	Dispose of rain water to new chamber	60	m	125	7,500.00
66	Surface water inspection chamber	4	nr	1,750	7,000.00
67	Aco multidrain	40	m	90	3,600.00
			Carried Forward £		754,328

Project: **Hadden Hill Retail Park, Didcot**

Code: **TWCM0743**

Ref: **Drive to Pod**

RIBA Stage 2 - Cost Plan

gleeds

Item	Description	Quantity	Unit	Rate	Total
			Brought Forward £		754,328
	External works Cont'd				
	Furniture				
68	Covered cycle hoops	9	nr	350	3,150.00
69	Bench; assumed timber	1	nr	350	350.00
70	Round picnic bench	8	nr		Excluded
71	Bin store	1	nr	3,500	3,500.00
72	AC enclosure	1	nr		Excluded
73	Allowance for bat boxes	1	item	350	350.00
	Hard landscaping				
74	Tactile paving; Pedestrian	400	m²	150	60,000.00
75	Kerbs to pedestrian path	136	m	95	12,920.00
76	Asphalt laid to new carparking spaces	142	m²	65	9,230.00
77	Bollards; 27nr drawn assume 30 - static	30	nr	250	7,500.00
78	Line painting including zebra crossing	1	item	2,500	2,500.00
	Soft landscaping				
79	New trees; including root protection and accessories (assumed saplings)	7	nr	550	3,850.00
80	Ornamental shrub planting	17	m²	100	1,700.00
81	Shrub hedging	28	m	50	1,400.00
82	Raised rain garden planting; including planter	6	m²	350	2,100.00
83	Ornamental bark mulch	0	m²	120	-
84	Grass	266	m²	20	5,320.00
85	Irrigation to planting areas - no indication	1	item		Excluded
86	2 years maintenance	2	nr	2,500	5,000.00
	External services, including external lighting				
87	External call point	1	item	15,000	15,000.00
88	Car charge points - active	2	nr	3,500	7,000.00
89	External lighting	1	item	10,000	10,000.00
90	External lighting; BWIC	1	item	1,000	1,000.00
		Total - To Estimate Summary £			**906,198**

Project : Hadden Hill Retail Park, Didcot

Code: TWCM0743

Ref: Drive to Pod

Schedule of Inclusions and Exclusions

gleeds

Ref	Item	Included	Excluded	Not Applicable	Comments
		✓	X	X	
1	Costs - In connection with land / site acquisition		X		
2	Costs - In connection with funding of project		X		Including any finance charges
3	Fees - In connection with Planning		X		
4	Costs - Demolition works	✓			
5	Costs - Construction of Shell and Core	✓			
6	Programme - Costs in connection with phasing / section completions		X		Project assumed to be completed in one phase of works
7	Construction Risks - Discovery of archaeological remains		X		
8	Construction Risks - Discovery of unexploded devices		X		
9	Construction Risks - Extra cost of disposing of hazardous and non-hazardous excavated material		X		
10	Construction Risks - Removal of asbestos		X		
11	Costs - Direct works by Employer		X		
12	Employer Risks - Effects of exchange rates		X		
13	Employer Risks - Effects of inflation		X		
14	Construction Risks - Removal of toxic waste		X		
15	Construction Risks - Treatment of invasive plant growth		X		
16	Construction Risks - Protection of 'Protected' trees		X		
17	Construction Risks - Dealing with presence of endangered species		X		
18	Construction Risks - Restricted working hours and/or routines		X		
19	Construction Risks - Works in connection with party wall awards			X	
20	Construction Risks - Costs in connection with diversion of existing services (Gas only)	✓			Gas included in Cost Plan
21	Construction Risks - Costs in connection with upgrading existing services		X		Connections only
22	Costs - In connection with fittings, furnishings and equipment		X		Shell only
23	Fees - In connection with Post-Novation Project and Design Team consultants		X		
24	Fees - In connection with Specialist consultants		X		
25	Fees and Charges - In connection with Site investigations		X		
26	Fees - In connection with Specialist support consultants (including Letting agents, Legal, Tax adviser, etc.) investigation fees and charges		X		
27	Fees - Main Contractor's Pre-Construction fees		X		
28	Fees - In connection with Main Contractor's design consultants	✓			
29	Fees - In connection with Building Control		X		
30	Fees - In connection with oversailing rights		X		
31	Fees - In connection with party wall awards		X		
32	Fees - In connection with rights of lights agreements		X		
33	Fees - In connection with other agreements between Client and neighbours to facilitate project completion		X		
34	Fees - Building scheme registration fees (e.g. NHBC Buildmark)		X		
35	Fees - In connection with licences, permits and agreements not normally paid by Contractor		X		
36	Charges - Adoption charges in connection with highways		X		
37	Costs - In connection with maintenance of highways		X		

Project : Hadden Hill Retail Park, Didcot

Code: TWCM0743

Ref: Drive to Pod

Schedule of Inclusions and Exclusions

gleeds

Ref	Item	Included	Excluded	Not Applicable	Comments
		✓	X	X	
38	Charges - Adoption charges in connection with services – i.e. sewerage, water, electricity and gas		X		
39	Costs - In connection with maintenance of services – i.e. sewerage, water, electricity and gas		X		
40	Contributions - Direct financial contributions in connection with planning consent - i.e. Section 106 and Section 278 contributions		X		
41	Costs - In connection with maintenance of environmental improvement works		X		
42	Costs - Works outside the boundary of the site / working area		X		
43	Insurances - In connection with the works; to be taken out by the Employer, including insurance premium tax (IPT)		X		
44	Fees and Charges - In connection with fieldwork carried out by archaeologists		X		
45	Fees and Charges - In connection with fieldwork carried out by specialists		X		
46	Costs - Tenant's costs		X		
47	Contributions - Tenant's contributions		X		
48	Marketing Costs - Generally including services and operating costs		X		
49	Tax - Value Added Tax (VAT)		X		
50	Tax - Capital Allowances		X		
51	Tax - Other tax allowances		X		
52	Incentives - Grants and taxation relief		X		
53	Renewable energy products		X		Other than PV panels included in cost plan.
54	Off-site infrastructure upgrades including sub-stations		X		
55	CCTV installations		X		
56	Enhancement necessary to achieve a specific Breeam rating		X		
57	Costs related to political and economic changes		X		
58	Consequences of the coronavirus (COVID-19) outbreak		X		Please refer to notes included under section 8 (Basis of Costs)
59	Secure by Design		X		
60	Enhanced Energy Performance requirements over and above Building Regulations		X		
61	Connection, infrastructure or future proofing workings relating to an Local DEN (District Energy Network)		X		
62	SUDS & Attenuation	✓			Other than where noted in the cost plan
63	Pumping station installations / upgrades		X		
64	Flood risk works		X		
65	Diversion works to existing water course		X		
66	Allowance for achieving a Nett Zero Carbon development		X		
67	Allowances for external wall type 1		X		None indicated on drawings but present in drawing key
68	Branding signage excluded		X		

gleeds.com