thornton-firkin
Project Managers - Cost Consultants

CONSTRUCTION OF NEW UNITS
LONG CAUSEWAY
LEEDS

STAGE 2 ESTIMATE – Rev B

August 2025 **1891.02**

THORNTON-FIRKIN LLP
Chartered Surveyors, Construction Consultants
Old Brewery Court
157 Sandyford Road
Newcastle upon Tyne
NE2 1XG

CONSTRUCTION OF NEW UNITS
LONG CAUSEWAY
LEEDS

STAGE 2 ESTIMATE – REV B

NOTES

1 This budget estimate is based on the following information:-

- GTH Architects Drawings GTH-01

ZZ-DR-A 2050B	Site Location Plan
XX-DR-A 2052A	Existing Site Location Plan
ZZ-DR-A 2080A	Site Constraints Plan
ZZ-DR-A 2200A	Proposed Site Plan
GF-DR-A 2201A	Proposed Ground Floor Plan
01-DR-A 2203A	Proposed First Floor Plan
02-DR-A 2205A	Proposed Roof Plan
GF-DR-A 2210A	Unit 01 – Ground Floor Plan
01-DR-A 2211A	Unit 01 – First Floor Plan
GF-DR-A 2220A	Unit 02 – Ground Floor Plan
01-DR-A 2221A	Unit 02 – First Floor Plan
GF-DR-A 2230A	Unit 03 – Ground Floor Plan
01-DR-A 2231A	Unit 03 – First Floor Plan
GF-DR-A 2240A	Unit 04 – Ground Floor Plan
01-DR-A 2241A	Unit 04 – First Floor Plan
GF-DR-A 2250A	Unit 05 – Ground Floor Plan
01-DR-A 2251A	Unit 05 – First Floor Plan
GF-DR-A 2260A	Unit 06 – Ground Floor Plan
01-DR-A 2261A	Unit 06 – First Floor Plan
ZZ-DR-A 2400A	Proposed Typical Sections
ZZ-SK-A 9005A	Entrance Ramp Sketch

- Met Geo Environmental Topographical Survey Drawings
- Google Earth Images

2 The information available to us is at preliminary design stage only and the costings herein reflect this and should be viewed as establishing an approximate order of cost only.

3 This cost plan assumes that the works will be subject to further design by the Employer's designers and let via a competitive tender procurement route under a JCT Design and Build Contract

4 It has generally been assumed that the work can be undertaken during normal working hours.

5 In regard to the M&E Services costings, Thornton-Firkin have incorporated budget allowances on their interpretation of the works required based on previous projects.

6 No contingency sum has been included and it is believed that the Client will be allowing for a contingency separately.

7 It has been assumed that adequate power and water supplies are already available within the site and that new incoming services are not required. Allowances have been included for diverting existing services and relocating the sub-station.

8 This estimate has been prepared without detailed Structural or Services cost advice. The costs included in this budget estimate based on experience in previous similar schemes.

9 A Preliminaries allowance of 5.5% has been incorporated in the budget estimate. This is based on a similar tendered scheme where costs ranged from 3.5% to 6.15% of the construction costs.

10 A design Risk allowance of 2.5% has been incorporated in the budget estimate. This is based on similar schemes where the Contractor takes on responsibility for the design.

11 A number of Provisional allowances have been incorporated while further design development and investigation is progressed:-

- Intumescent paint for first floor steelwork and boundary wall to railway line
- Mansafe system to roof
- Surface water attenuation
- Diversion of electrical services and relocation of sub-station
- PV installation
- EC charger installation

12 Exclusions

- VAT
- Statutory Fees
- Professional fees
- Surveys and Reports
- Bio-diversity Net Gain requirements
- Future Inflation (priced at 3rd quarter 2025)
- Contingency sum (Client allowing for this separately)
- Abnormal foundations/ground conditions
- Removal of asbestos and other contaminates
- Removal of equipment/machinery, etc within existing buildings
- New utility supplies (allowances made for diversions only)
- Costs associated with working in close proximity to the railway line/liaising with Network Rail
- Dock levellers/loading bay canopies or the like

Thornton-Firkin LLP
1891.02
28th August 2025

Ref	Description	Quantity	Unit	Rate	Total £
	Long Causeway - Leeds				
	LONG CAUSEWAY, LEEDS				
	STAGE 2 COST PLAN				
	Demolition and Site Clearance				196,035
	New Shed Units				4,228,409
	External Works and Drainage				936,428
	External Services				137,000
	Preliminaries @ 5.5%			5.50	302,383
	Design Risk @ 2.5%			2.50	145,006
	EXCLUSIONS				
	Contingency (Client allowing for this separately)				
	VAT				
	Inflation				
	Professional Fees				
	Statutory Fees				
	Surveys and Reports				
	Bio-diversity Net Gain requirements				
	Removal of Asbestos or other Contaminants				
	Removal of Equipment or Fixtures within existing buildings				
	Abnormal foundations/piling				
	New utility supplies (allowances made for diversions only)				
	Costs associated with working in close proximity to the railway line/liaising with Network Rail				
	Dock levellers/loading bay canopies or the like				
	Total				**5,945,261**

Ref	Description	Quantity	Unit	Rate	Total £
	Demolition and Site Clearance				
	Demolish existing warehouse/industrial building down to slab level; maximum 7m height to eaves	3,548	m2	25.00	88,700
	Break out existing reinforced concrete slab and shallow foundations (pads, ground beams, etc)	3,548	m2	20.00	70,960
	Break out existing concrete slab/service yard areas	1,582	m2	15.00	23,730
	Break out existing tarmac access road/parking areas	1,975	m2	5.50	10,863
	Break out existing flag paving	93	m2	2.50	233
	Demolish existing brick retaining wall n.e 1500 high and grub up foundations	31	m	50.00	1,550
	Total				**196,036**

Ref	Description	Quantity	Unit	Rate	Total £
	New Shed Units				
	Substructure				822,775
	Frame				476,250
	Upper Floors				157,700
	Roof				503,710
	Stairs				171,000
	External Walls				547,100
	Windows and External Doors				150,000
	Internal Walls & Partitions				479,365
	Internal Doors				69,900
	Floor Finishes				66,755
	Ceiling Finishes				2,520
	Mechanical Services				162,225
	Electrical Services				619,109
	Total				**4,228,409**

Ref	Description	Quantity	Unit	Rate	Total £
	Substructure				
	Reinforced concrete foundations, pad bases and ground beams including all excavation, disposal, earthwork support concrete, reinforcement, etc	3,730	m2	25.00	93,250
	Reinforced concrete ground floor slab including all excavation, disposal, Type 1 sub-base, blinding, dpm, reinforcement, concrete with formed and induced joints	3,730	m2	175.00	652,750
	Cavity walls up to dpc level to perimeter	415	m	185.00	76,775
	Total				**822,775**

Ref	Description	Quantity	Unit	Rate	Total £
	Frame				
	Structural steelwork portal frame including fittings, erection, baseplates, etc	3,730	m2	125.00	466,250
	Allowance for intumescent paint to steel for first floor offices and boundary walls	1	IT	10,000.00	10,000
	Total				**476,250**

Ref	Description	Quantity	Unit	Rate	Total £
	Upper Floors				
	Composite flooring to first floor offices & welfare areas	775	m2	120.00	93,000
	Insulation & screed to first floor office & welfare areas	775	m2	80.00	62,000
	Removable infill floor to Stores at FF level within possible lift shaft	18	m2	150.00	2,700
	Total				**157,700**

Ref	Description	Quantity	Unit	Rate	Total £
	Roof				
	Composite cladding to roof including rooflights over factory area	3,730	m2	105.00	391,650
	Aluminium rainwater goods	3,730	m2	12.00	44,760
	Allowance for Mansafe system for safe roof access	3,730	m2	10.00	37,300
	Roof access hatches; Bilco E50 or similar; including all trimming, flashings, etc	6	nr	5,000.00	30,000
	Total				**503,710**

Ref	Description	Quantity	Unit	Rate	Total £
	Stairs				
	Steel staircase with half landings for access to intermediate and first floor welfare & office areas; 6m rise overall; including steel handrails and balustrades	6	nr	25,000.00	150,000
	Roof access CAT ladders with safety cage; average 11m overall height	6	nr	3,500.00	21,000
	Total				**171,000**

Ref	Description	Quantity	Unit	Rate	Total £
	External Walls				
	Feature composite cladding to front elevation; micro-rib or similar panels including all flashings, trims, etc; 11m height to haunch	197	m	1,650.00	325,050
	Composite cladding to side and rear elevations; trapezoidal panels including all flashings, trims, etc; 8m height to haunch	170	m	600.00	102,000
	Composite cladding to side elevations; trapezoidal panels including all flashings, trims, etc; 10m average height to haunch	50	m	750.00	37,500
	Blockwork to external walls and column casings up to 2300 above floor	417	m	150.00	62,550
	Allowance for cavity barriers, firestops, etc	1	IT	20,000.00	20,000
	Total				**547,100**

Ref	Description	Quantity	Unit	Rate	Total £
	Windows and External Doors				
	Steel personnel escape door to rear of each unit	6	nr	1,000.00	6,000
	Aluminium double glazed windows to offices and welfare areas of each unit	6	nr	3,500.00	21,000
	Aluminium double glazed entrance doors & screens to each unit	6	nr	5,000.00	30,000
	Allowance for feature entrance/canopy to each unit	6	nr	10,000.00	60,000
	Loading doors to each unit; electrically operated insulated roller doors with vision panels	6	nr	4,500.00	27,000
	Galvanised steel bollards to either side of loading doors to each unit	6	nr	1,000.00	6,000
	Total				**150,000**

Ref	Description	Quantity	Unit	Rate	Total £
	Internal Walls & Partitions				
	Dividing walls between Units; 140 blockwork; ave 10m to haunch height	111	m	1,400.00	155,400
	Firestopping to head	111	m	85.00	9,435
	Fire Rated walls to form Stair Core, Lift Shafts, Offices, etc	2,012	m2	140.00	281,680
	Non fire rated stud walls to form WC's, Stores, etc	334	m2	75.00	25,050
	IPS system to FF WC's	39	m2	200.00	7,800
	Total				**479,365**

Ref	Description	Quantity	Unit	Rate	Total £
	Internal Doors				
	Fire doors including ironmongery & decoration; from stair core to warehouse & office area of each unit and risers	36	nr	1,100.00	39,600
	Paint grade solid core doors including ironmongery and decoration; to WC and store areas of each unit	30	nr	650.00	19,500
	Paint grade solid core double doors including ironmongery and decoration; to WC and store areas of each unit	12	nr	900.00	10,800
	Total				**69,900**

Ref	Description	Quantity	Unit	Rate	Total £
	Floor Finishes				
	Floor finishes to office, core & welfare areas; entrance matting, carpet to offices & entrance areas with vinyl to wc's; skirtings	1,027	m2	65.00	66,755
	Total				**66,755**

Ref	Description	Quantity	Unit	Rate	Total £
	Ceiling Finishes				
	Lay in grid suspended ceilings to wc areas	72	m2	35.00	2,520
	Total				**2,520**

Ref	Description	Quantity	Unit	Rate	Total £
	Mechanical Services				
	Hot and cold water installation per Unit	6	nr	10,000.00	60,000
	Mechanical Ventilation installation per Unit	6	nr	5,000.00	30,000
	Sanitaryware and above ground drainage to Acc Washrooms	6	nr	5,000.00	30,000
	Sanitaryware and above ground drainage to Clearers Cupd	6	nr	750.00	4,500
	Sanitaryware and above ground drainage to WC's	12	nr	2,500.00	30,000
	Allowance for BWIC Mechanical Services @ 5%			5.00	7,725
	Total				**162,225**

Ref	Description	Quantity	Unit	Rate	Total £
	Electrical Services				
	Distribution cabling & switchgear	4,523	m2	17.00	76,891
	General power installation	4,523	m2	6.50	29,400
	Lighting to warehouse, office areas and emergency lighting	4,523	m2	20.00	90,460
	External lighting	4,523	m2	8.00	36,184
	CCTV installation	4,523	m2	1.50	6,785
	Fire detection & alarm systems	4,523	m2	17.00	76,891
	Lightning protection system	4,523	m2	2.80	12,664
	Containment	4,523	m2	4.50	20,354
	Allowance for PV installation	1	IT	60,000.00	60,000
	Allowance for electrical vehicle chargers (allow for 1nr rapid charger and 1nr standard charger per Unit)	6	nr	30,000.00	180,000
	Allowance for BWIC Electrical Services @ 5%			5.00	29,481
	Total				**619,110**

Ref	Description	Quantity	Unit	Rate	Total £
	External Works and Drainage				
	External Works				
	New tarmac access road; including excavation, Type 1 sub-base, kerbs, etc	1,158	m2	180.00	208,440
	New tarmac service yards; including excavation, Type 1 sub-base, kerbs, etc	1,023	m2	180.00	184,140
	Parking Areas - block paved or tarmac; including excavation, Type 1 sub-base, kerbs, etc	608	m2	120.00	72,960
	Concrete slab for new sub-station; including excavation, Type 1 sub-base, kerbs, etc	58	m2	120.00	6,960
	Paved areas to front of house - slab/block paving or tarmac; including excavation, Type 1 sub-base, kerbs, etc	668	m2	110.00	73,480
	Paved areas to rear & sides of building; including excavation, Type 1 sub-base, kerbs, etc	458	m2	90.00	41,220
	Retaining walls; assumed average 1.5m high	230	m2	275.00	63,250
	Allowance for additional excavation into bank for new retaining walls and disposal off site	1	IT	10,000.00	10,000
	Clear debris, prune trees/shrubbery and generally tidy up area to North West of site	806	m2	2.50	2,015
	Cut down existing tree to North West corner and remove tree stump	1	nr	400.00	400
	Clear debris, prune trees/shrubbery and generally tidy up area to front of site along A63	675	m2	2.50	1,688
	Allowance for white lining/road markings	1	IT	5,000.00	5,000
	Cycle hoops	13	nr	100.00	1,300
	New entrance gates; manual swing gates	1	IT	20,000.00	20,000
	Allowance for new signage/totem bases (signage not included)	1	IT	10,000.00	10,000
	Drainage				
	Surface and foul water drainage to new Units	3,741	m2	15.00	56,115
	Surface water drainage to hard paved external areas	3,973	m2	20.00	79,460
	Allowance for stormwater attenuation	1	IT	100,000.00	100,000
	Total				**936,428**

Ref	Description	Quantity	Unit	Rate	Total £
	External Services				
	Allowance for diversion work to electrical services/relocation of sub-station	1	IT	100,000.00	100,000
	Allowance for diversion work to existing water supply	1	IT	10,000.00	10,000
	Allowance for new electrical supply into each Unit	6	nr	2,500.00	15,000
	Allowance for new water supply to each Unit	6	nr	1,000.00	6,000
	Allowance for new Telecom supply to each Unit	6	nr	1,000.00	6,000
	Total				**137,000**